DECODED:

Test Your Knowledge



From the well-known blog idighardware.com,
Lori Greene brings some much-needed clarity to codes.

BY LORI GREENE, AHC/CDC, CCPR, FDHI

	ACROSS
1.	NFPA 80 limits the clearance at the head, jambs, and meeting stiles of a fire door to 1/8".
	The 2010 ADA requires an automatic door to have the same maneuvering clearance as a
	manual door unless the operator has power.
6.	The IBC does not allow delayed egress locks to be used in, Educational, or High Hazard
	occupancies.
7.	NFPA 80 requires the base material for hinges to be, unless otherwise tested and listed
9.	A door with a closer and a hold-open released by the fire alarm system is consideredclosing.
14.	Signage stating "This door to remain unlocked when building is occupied" is required when
	operated locks are installed.
15.	The Fair Housing Act applies to multi-family buildings with or more dwelling units.
17.	In the IBC and NFPA 101, fire door assemblies are called protectives.
19.	In NFPA 101, a multiple occupancy in which two or more occupancy types are separated by fire
	resistance-rated construction is a occupancy.
	A door with a door closer and no hold-open is consideredclosing.
22.	NFPA 101 now requires annual inspections of some egress doors in Assembly,,
	Day Care, and Residential Board and Care occupancies.
24.	warning on hardware leading to hazardous areas is not required by the ADA or
	ICC A117.1 accessibility standards.
26.	The portion of the exit access traveled before two distinct paths of egress become available is
~-	called the path of travel.
	A is required for pairs of fire doors with automatic flush bolts.
30.	Panic hardware is required for rooms containing electrical equipment with 800 or
21	more per the 2014 edition of NFPA 70. According to NFPA 101 and the IBC, certain units in hospitals and nursing homes may now lock
31.	their egress doors using a lock if the applicable requirements are met.
33	The portion of a means of egress between the end of the exit and the public way is called the
<i>J</i> J.	exit
34.	Kick plates mounted in the bottom inches of fire doors do not require a label.
	NFPA 101 requires all exits, including stairways and doors, in Educational and Day Care occupancies
	to be inspected by principals, teachers, or staff to ensure that they are in proper condition.
37.	NFPA 105 is the standard for doors.
	The IBC now requires luminous egress path markings for doors leading out of an exit enclosure
	in many buildings.
40.	NFPA 101 requires panic hardware for Assembly, Educational, and Day Care occupancies with
	an occupant load of or more.
43.	Egress doors must with one operation.
	The actuating portion of panic hardware must extend across at least $___$ the width of the door.
	UL 294 is a certification for access system components.
	An additional hinge is required for each inches of height on a fire door.
48.	The accessibility standards require doors to close from degrees to 12 degrees in a
	minimum of five seconds.
	DOWN

2. Deficiencies found during a fire door inspection must be repaired without __

3. In 2003, 100 people were killed in a tragic fire at the _____ Nightclub in Rhode Island.4. The _____ develops and publishes more than 300 consensus codes and standards.

1 2 3 4 7 13 14 10 15 17 18 10 22 17 27 31 32 27 33 36 38 39 39	5 6 11 12 16 19 20 21 23 24 25 30 37 35 40 41
42	43 44 45
46	47
	48
 A doctor's office would be considered a occupancy. means acceptable to the Authority Having Jurisdiction. A horizontal exit leads to an area of 	 30. To calculate the occupant load of a space, you must divide the by the occupant load factor. 32. In the 2015 IBC, the section called Access Controlled Egress
10. According to the 2013 edition of NFPA 80, fire door assemblies must be inspected annually, and also upon installation and	Doors has been changed to Release of Electrically Locked Egress Doors. 34. An electric strike used on a fire door assembly must be
11. In 1911, 146 workers were killed in the Shirtwaist Factory fire.12. An interior, non-fire-rated door is required to open with a	fail 35. In the IBC (2009 and later), an Electromagnetically Locked Egress Door has a mag-lock that is released bymounted
maximum of pounds of force. 13. Chapter 6 of NFPA 80 contains the requirements for Swinging	hardware. 36. Residential units with an occupant load of 10 or fewer
Doors with Hardware. 16. According to NFPA 70, panic hardware is required for rooms containing electrical equipment with 600 or more.	may typically have separate locks that require two operations to unlatch.39. Glazing used in doors and sidelites, including fire door
18. A stairwell enclosed by fire-resistance-rated construction and opening protectives to provide a protected path of egress travel is an	assemblies, is now required by the IBC to beresistant. 41. The clear opening height of a door is typically required to be a minimum of inches.

See page 59 for answers

21. The exit _____ leads from an occupied portion of a building

23. Most access control work will require a _____ from the AHJ.

25. For both egress and accessibility, the minimum clear opening

width required for most doors is thirty-____ inches.

29. The clearance at the bottom of a fire door is limited to __

28. The IBC, IFC, and A117.1 are publications of the ___

of an inch.

to an exit.

42. The minimum _____ of a latch bolt for a fire door is shown


43. The test used to measure air/smoke infiltration is _____ 1784.

45. According to the 2006 edition of the IBC and subsequent editions,

panic hardware is required for Assembly and Educational

occupancies with an occupant load of _____ or more. dh

on the fire door label.



a d index

Akron Hardware	25	
Advantage Lites & Louvers	2	
Boyle & Chase		
Doors & Hardware House Ads		
2015 Education Schedule	28-29	
Advertising Guide 2015	39	
Allstate	21	
CE1401 Codes and Standards	37	
DHI Classified	57	
DHIndustry Careers	49	
Foundation Contributors Thank You	54-55	

Social Networks	56
TISC Insurance	53
Hager Companies	7
Midwest Wholesale Hardware	Inside Back Cover
PDQ	41
Salsbury Industries	57
Security Lock Distributors	Insert, 15, Back Cover
Top Notch Distributors	5
TownSteel, Inc	13
VT Industries	Inside Front Cover-1